

*Tips*

## **Vehicles and Mobile Plant**

*Make sure drivers on site  
can see you*



# Vehicles and Mobile Plant

## **Keep clear access for vehicles coming on site:**

- make sure someone is there to signal backing vehicles
- make eye contact with drivers so you know that they have seen you
- drivers should STOP when the spotter is not in view
- only operate plant you're trained and competent to use
- stay visible to the operator while working near mobile plant and equipment – diggers, hiabs, concrete trucks etc
- ensure hi-vis clothing is reflective and zipped up when around vehicles/mobile plant
- always keep clear of the 'swing area' of mobile plant, cranes or excavators and the tipping area behind trucks
- draw up a site plan to help plan deliveries on site; try to avoid peak traffic when planning deliveries
- all contractor vehicles to be parked legally and not left obstructing paths, berms, access ways or road access to other properties.